

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21544-00-00
Spot: NWSESESE Sec/Twnshp/Rge: 36-21S-16W
420 feet from S Section Line, 420 feet from E Section Line
Lease Name: PROSSER Well #: 1
County: PAWNEE Total Vertical Depth: 3905 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3840		WITH 2 SX CMT
SURF	8.625	972		WITH 450 SX CMT
PROD	5.5	3896	1828	WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/05/2010 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT INC. Phone: (620) 793-2540

Proposed Plugging Method: SAND TO 3840' & 5 SX CMT OR CIBP @ 3840' & 2 SX CMT OR PUMP 300-400# HULLS & 30 SX CMT. PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/05/2010 11:18 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 3840' WITH 2 SX CMT. 1ST PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
3894	3905		ARBUCKLE

INVOICED
DATE 3/25/10
INV. NO. 2010060985

RECEIVED
MAR 11 2010

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

KCC WICHITA

Plugged through: CSG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
MAR - 8 2010
KCC DODGE CITY

Edm. C. 2/5