

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-01539-00-00
Spot: SESENW Sec/Twnshp/Rge: 12-25S-13W
2310 feet from N Section Line, 2310 feet from W Section Line
Lease Name: NORTH LEESBURG UNIT Well #: 101
County: STAFFORD Total Vertical Depth: 4124 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3126		
CIBP		4054		
SURF	10.75	464		WITH 350 SX CMT
PROD	7	4079	0	WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/25/2010 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3075' & 7 SX CMT WITH DUMP BAILER. PERFORATE 7" @ 760'. CIRCULATE CMT FROM 760-0'.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/25/2010 4:44 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 2950' & 7 SX CMT WITH DUMP BAILER. PRESSURED TESTED CASING FROM 2900' TO 0' TO 425 PSIG. PERFORATED 7" @ 760'. PUMPED DOWN 7" WITH 440 SX CMT AND HAD GOOD CIRCULATION UP 10 3/4". DID NOT GET CMT TO SURFACE. WAITED 1 HOUR ON MORE CMT. PUMPED 50 SX CMT & HAD GOOD CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4032	4042		
3758	3768		
3747	3750		
3732	3738		
3718	3723		
3704	3708		
3688	3693		
3062	3068		

INVOICED
DATE 3/25/10
INV NO 2010060786

RECEIVED
MAR 11 2010

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

KCC WICHITA

Plugged through: CSG

District: 01

RECEIVED
MAR - 2 2010
KCC DODGE CITY

Signed Richard M. Fasel
(TECHNICIAN)