

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-067-20075-00-00  
Spot: NWNWSENW Sec/Twnshp/Rge: 21-29S-36W  
1495 feet from N Section Line, 1550 feet from W Section Line  
Lease Name: HAGERMAN GEORGE GU Well #: 2  
County: GRANT Total Vertical Depth: 2790 feet

Operator License No.: 5952  
Op Name: BP AMERICA PRODUCTION COMPANY  
Address: 2225 W OKLAHOMA AVE  
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2650		
SURF	8.625	669		WITH 191 SX CMT
L1	5.5	2801		WITH 177 SX CMT
PROD	5.5	2801	0	WITH 177 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/03/2010 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/03/2010 12:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

\*\*RODS, TBG, & PUMP FISH LEFT IN HOLE. TOP OF RODS @ 1363', TOP OF FISH @ 1358'. \*\* PERFORATE 5 1/2" CASING @ 700'. RIH W/TBG TO 1350' & PUMPED 140 SX CMT & 100# HULLS. POOH W/TBG, TIED ONTO 5 1/2" & PUMPED 200 SX CMT FILLING 5 1/2" & 5 1/2" X 8 5/8" ANNULUS, CIRCULATED CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2771	2780		
2752	2756		
2744	2750		
2732	2740		
2717	2724		

INVOICED  
DATE 3/24/10  
INV. NO. 2010060942

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 23 2010  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed Jack MacLaskey  
(TECHNICIAN)

RECEIVED  
MAR 11 2010

KCC DODGE CITY

Form CB-273