

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-00345-00-00
Spot: SWSWSWNE Sec/Twnshp/Rge: 32-27S-37W
2640 feet from S Section Line, 2640 feet from E Section Line
Lease Name: WILLIAMS ARTIE MAY Well #: 1
County: GRANT Total Vertical Depth: 2585 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 W OKLAHOMA AVE
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1890		
CIBP		2050		
SURF	10.75	645		WITH 375 SX CMT
L1	5.5	2361		
PROD	7	2370	0	WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/05/2010 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/05/2010 11:30 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 1890'. (UNABLE TO GET BELOW 1912') RAN BOND LOG. TOC @ 640'.
PERFORATE 7" @ 600'. RIH W/TBG TO 1880' & PUMP 193 SX CMT. POOH W/TBG.
TIE ONTO 7" CASING & PUMP 241 SX CMT FILLED 7" & 7" X 10 3/4" ANNULUS TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2530	2580		
2479	2511		
2422	2450		
2370	2394		

INVOICED
DATE 3/24/10
INV. NO. 2010060942

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 23 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
MAR 11 2010

Signed Jack MacLaskey
(TECHNICIAN)

KCC DODGE CITY