

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20073-00-00  
Spot: NWSE Sec/Twnshp/Rge: 9-27S-31W  
2017 feet from S Section Line, 2004 feet from E Section Line  
Lease Name: FRANK A Well #: 1  
County: HASKELL Total Vertical Depth: 5285 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2600		WITH 2 SX CMT
CIBP		5000		WITH 2 SX CMT
SURF	8.625	900		WITH 400 SX CMT
PROD	5.5	5150	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/17/2010 12:30 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: GREG KLAUS Company: BEREXCO INC. Phone: (316) 265-3311

Proposed Plugging Method: CIBP @ 4400' & CIBP @ 2600'. PERFORATE AT 950' CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/18/2010 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5000' WITH 2 SX CMT. TAGGED FILL UP AT 5040'. CIBP @ 2600' WITH 2 SX CMT. TEST CASING TO 300# & HELD. PERFORATE AT 950'. CASING WENT ON VACUUM. FLOW OUT ANNULUS. CIRCULATED CMT THROUGH PERFS AT 950' TO SURFACE WITH 250 SX CMT. CASING & ANNULUS STAYED FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
5086	5096		

RECEIVED  
MAR 10 2010  
KCC WICHITA

INVOICED  
DATE 3/25/10  
INV. NO. 2010060997

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED  
MAR - 2 2010  
KCC DODGE CITY

Signed Ken Jehlik  
(TECHNICIAN)

Form CP-2/8