

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23120-00-01
Spot: SÉSWSW Sec/Twnshp/Rge: 7-13S-19W
372 feet from S Section Line, 4389 feet from E Section Line
Lease Name: WOLF Well #: 2-7
County: ELLIS Total Vertical Depth: 3764 feet

Operator License No.: 5363

Op Name: BEREXCO, INC.

Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	366	0	w/210 sxs cmt
PROD	5.5	1102	0	w/270 sxs cmt

Well Type: WSW

UIC Docket No:

Date/Time to Plug: 03/15/2010 11:00 AM

Plug Co. License No.: 5363

Plug Co. Name: BEREXCO, INC.

Proposal Rcvd. from: CURT GABEL

Company: BEREXCO, INC.

Phone: (316) 265-3311

Proposed Plugging Method: Ordered 160sxs 60/40 pozmix - 4% gel - 200# hulls.
Perfs at 950' and 1050'.
Sanded off bottom with 1680 lbs of sand.

Plugging Proposal Received By: CASE MORRIS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 03/15/2010 1:00 PM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing to 736' - pumped 75 sxs cement - good circulation of cement.
Pulled tubing out - tied onto 5 1/2" - squeezed with 10 sxs cement.
Shut in at 400# P.S.I.
Backside full of cement.

INVOICED
DATE 3/25/10
INV. NO. 2010060997


Remarks: ALLIED CEMENTING COMPANY-TICKET #36351.

Plugged through: TBG

RECEIVED
MAR 22 2010
KCC WICHITA

District: 04

Signed



(TECHNICIAN)

cm

MICHAELIS CORPORATION

REPLACEMENT CARD


7-13-19W
SE SW SW

247 #2-7 WOLF

KS 67201

ED TIGER DRILLING CTY ELLIS

MARRY BOOKLESS FIELD PFEIFER NO. CONF



LB SPD 9/2/82 CARD ISSUED 3/24/83 IP D&A/ARB
3L 9/12/82

Depth/Datum
..... 3353-1277
..... 3395-1319
..... 3747-1671
..... 3764-1688

API 15-051-23,120

8 5/8 " 366/210SX
 DST (1) 3346-3440 (HEEB, LKC) / 30-45-30-45, REC 15' DM, W/
 SCUM OIL, SIP 1127-1065#, FP 26-26 / 35-35#
 DST (2) 3438-84 (LKC) / 30-45-60-90, REC 63' OIL SPKD M, SIP
 819-801#, FP 26-26 / 44-44#
 DST (3) 3500-70 (LKC) / 30-45-60-90, REC 30' DM, SIP 143-
 143#, FP 62-62 / 71-71#
 DST (4) 3563-3640 (LKC) / 30-45-60-90, 92' GIP, REC 154'
 O&GCM, SIP 1160-1098#, FP 44-53 / 80-98#

INFO RELEASED: 11/15/84 - WAS D&A - TIGHT HOLE

COPYRIGHT 1984
 ENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS