

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20846-00-00

Spot: NWNWNW

Sec/Twnshp/Rge: 17-17S-10W

4969 feet from S Section Line, 4916 feet from E Section Line

Lease Name: PETERMAN

Well #: 1

County: ELLSWORTH

Total Vertical Depth: 3341 feet

Operator License No.: 7383

Op Name: GRADY BOLDING CORPORATION

Address: PO BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

SURF	8.625	309		250 SX
------	-------	-----	--	--------

PROD	5.5	3334		175 SX
------	-----	------	--	--------

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/01/2010 9:00 AM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: GRADY BOLDING

Company: GRADY BOLDING CORP

Phone: (620) 564-2240

Proposed
Plugging
Method:

SEE BELOW

Plugging Proposal Received By: JEFF KLOCK

Witness Type: PARTIAL

Date/Time Plugging Completed: 03/01/2010 11:30 AM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 3200' AND CAP WITH 5 SX'S CEMENT. CUT CASING @ 1621' AND PULL TO 971' AND PUMP 50 SX'S CEMENT WITH 100 #S COTTON HULLS - DID NOT GET CIRCULATION. PULL CASING TO 850' AND PUMP 35 SXS CEMENT WITH 200# COTTON HULLS - DID GET CIRCULATION. PULL CASING TO 600' AND PUMP 35 SX'S CEMENT. PULL CASING TO 360' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF. USED 220 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3262	3266	CSG	

INVOICED

DATE 3/24/10

INV. NO. 2010060958

RECEIVED

MAR 11 2010

KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. QUALITY CEMENT TICKET #3625

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)