

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-20755-00-00  
Spot: SENWSESE Sec/Twnshp/Rge: 31-19S-33W  
880 feet from S Section Line, 720 feet from E Section Line  
Lease Name: VULGAMORE Well #: 1-31  
County: SCOTT Total Vertical Depth: 4840 feet

Operator License No.: 9855  
Op Name: GRAND MESA OPERATING COMPANY  
Address: 1700 N WATERFRONT PKWY BLDG 600  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	222		WITH 170 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/05/2010 9:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: TONY MARTIN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 2210' WITH 50 SX CMT. 2ND PLUG AT 1170' WITH 80 SX CMT. 3RD PLUG AT 570' WITH 40 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE  
Date/Time Plugging Completed: 03/05/2010 1:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 2210' WITH 50 SX CMT. 2ND PLUG AT 1170' WITH 80 SX CMT. 3RD PLUG AT 570' WITH 40 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

INVOICED  
DATE 3/24/10  
INV. NO. 2010060959

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

RECEIVED

MAR 11 2010

KCC WICHITA

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED

MAR - 5 2010

KCC DODGE CITY

Form CP-24