

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-00409-00-01
Spot: SESWSWNW Sec/Twnshp/Rge: 11-27S-15W
2310 feet from N Section Line, 330 feet from W Section Line
Lease Name: COVEY B Well #: 1
County: PRATT Total Vertical Depth: 4520 feet

Operator License No.: 33936
Op Name: GRIFFIN, CHARLES N.
Address: 177 OLD HWY 40 PO BOX 670
BYERS, CO 80103

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	290		WITH 300 SX CMT
PROD	4.5	4500	2020	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/04/2010 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4340' & 4 SX CMT. PLUG AT 1000' WITH 15 SX GEL WATER & 50 SX CMT. PLUG AT 320' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/04/2010 11:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4340' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT W/3% CC & 50# HULLS. 2ND PLUG AT 320' WITH 50 SX CMT & 50# HULLS. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4398	4402		

INVOICED
DATE 3/24/10
INV. NO. 2010060960

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 23 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

Signed Steve Pfeifer
(TECHNICIAN)

RECEIVED
MAR 11 2010
KCC DODGE CITY