

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22043-00-01
Spot: SWSE Sec/Twnshp/Rge: 31-29S-13W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: DORIS LAMBERT B Well #: 1-31
County: PRATT Total Vertical Depth: 4765 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4630 | | |
| SURF | 13.38 | 213 | | WITH 225 SX CMT |
| PROD | 4.5 | 4764 | 2200 | WITH 225 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2010 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4400' & 4 SX CMT. PLUG AT 810' WITH 50 SX CMT. PLUG AT 240' WITH 75 SX CMT. PLUG AT 40-0' WITH 20 SX CMT

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 03/16/2010 1:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

SAND TO 4400' WITH 4 SX CMT. 1ST PLUG AT 810' WITH 20 SX GEL, 50 SX CMT & 100# HULLS. 2ND PLUG AT 240' WITH 75 SX CMT & 50# HULLS. 3RD PLUG AT 40' WITH 50 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|-------------------|
| 4638 | 4640 | | SIMPSON SAND |
| 4534 | 4542 | | VIOLA |
| 4524 | 4530 | | VIOLA |
| 4450 | 4458 | | MISSISSIPPIAN- KI |

INVOICED
DATE 3/24/10
INV. NO. 2010060961

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 23 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

Signed Steve Durrant
(TECHNICIAN)

RECEIVED
MAR 18 2010

KCC DODGE CITY