

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22038-00-00
Spot: E2SWSW Sec/Twnshp/Rge: 32-29S-13W
510 feet from S Section Line, 4290 feet from E Section Line
Lease Name: SCHRIVER A Well #: 1-32
County: PRATT Total Vertical Depth: 4813 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	13.38	286		WITH 275 SX CMT
PROD	4.5	4812	2200	WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/17/2010 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4480' & 4 SX CMT. PLUG AT 840' WITH 50 SX CMT. PLUG AT 300' WITH 85 SX CMT. PLUG AT 40' WITH 50 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: NONE
Date/Time Plugging Completed: 03/17/2010 4:15 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SAND TO 4480' & 4 SX CMT. 1ST PLUG AT 810' WITH 26 SX GEL, 50 SX CMT W/3% CC & 100# HULLS. 2ND PLUG AT 315' WITH 85 SX CMT & 100# HULLS. 3RD PLUG AT 40' WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4534	4550		

INVOICED
DATE 3/24/10
INV. NO. 2010060961

Remarks: 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

Signed

Jerry W. Stapleton
PIRE II (TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 23 2010
CONSERVATION DIVISION
WICHITA, KS

RECEIVED

MAR 18 2010

KCC DODGE CITY