

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-23649-00-00
Spot: SESENWSW Sec/Twnshp/Rge: 30-23S-22E
1513 feet from S Section Line, 1141 feet from W Section Line
Lease Name: STEWART Well #: 2
County: BOURBON Total Vertical Depth: 706 feet

Operator License No.: 31519
Op Name: JACKSON, LELAND DBA LONE JACK O
Address: 509 E WALNUT ST
BLUE MOUND, KS 66010

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.25	20		5 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/18/2009 8:00 AM
Plug Co. License No.: 31519 Plug Co. Name: JACKSON, LELAND DBA LONE JACK OIL CO.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: Place a 50' plug at TD, Place a 50' plug at 500', circulate cement from 200' to surface.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE
Date/Time Plugging Completed: 12/18/2009 5:00 PM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe inside 6.25" surface casing to 706'. Pumped 13 sacks of portland cement through the 1" pipe. Pulled up to 500' and pumped 13 sacks of cement. Pulled up to 200' and circulated cement to surface. A total of 39 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED

MAR 18 2010 RD

KCC Chanute Dist. #3

INVOICED

DATE 3/24/10

INV. NO. 2010060963

Remarks:

Plugged through:

District: 03

Signed _____

PIRT II
(TECHNICIAN)

RECEIVED Form CP-2/3

MAR 22 2010

KCC WICHITA