

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-14674-00-00  
Spot: SWNESW Sec/Twnshp/Rge: 24-20S-11W  
1650 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: SESSLER C Well #: 3  
County: BARTON Total Vertical Depth: 3259 feet

Operator License No.: 31528  
Op Name: KELSO, MIKE OIL, INC.  
Address: PO BOX 467  
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	167	0	w/unknown sxs cmt
L1	4.5	3233		
PROD	6	3247	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/03/2010 1:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/03/2010 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded bottom and topped with 4 sxs cement - plug back to 3183'.  
Perfed at 900' - 440' 160'.  
Ran tubing to 3000' - pumped 150 sxs cement.  
Pulled tubing to 700' - pumped 60 sxs cement - circulated to surface.  
Pulled tubing. Tied to surface - pumped 15 sxs cement.  
Started pushing out around the head.

Perfs:

INVOICED  
DATE 3/25/10  
INV. NO. 2010060965

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 08 2010

CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN) CM

MAR 05 2010