

\$ 70.⁰⁰

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19217-00-00
Spot: SWNENWSW Sec/Twnshp/Rge: 5-34S-6E
2172 feet from S Section Line, 4498 feet from E Section Line
Lease Name: WALDSCHMIDT A Well #: 2
County: COWLEY Total Vertical Depth: 2157 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	1510		
CIBP	5.5	1791		
SURF	8.625	216		216 SX
PROD	5.5	2153	960	140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/07/2009 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: MIKE ANSTINE Company: W D SHORT OIL CO., LLC Phone: (316) 218-1822

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 08/07/2009 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SET CIBP @ 1,510', DUMP BAILED 2 SXS CEMENT ON TOP. CUT 5-1/2" CASING @ 960', LAYED CASING DOWN. RIH W/TBG @ 352', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, & MIXED & PUMPED 130 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 8-7-2009 @ 5:00 PM. CONSOLIDATED CEMENT TICKET #20896.

Perfs:

Top	Bot	Thru	Comments
1670	1688	CSG	
1625	1645	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 25 2010
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 3/23/10
INV. NO. 2010060874

Remarks:

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

15K