

\$ 79.89

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21199-00-00
Spot: SEWNESW Sec/Twnshp/Rge: 25-31S-2E
2055 feet from S Section Line, 3360 feet from E Section Line
Lease Name: CHAMBERLAIN Well #: 1
County: SUMNER Total Vertical Depth: 2458 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	255		SURFACE
PROD	4.5	2434	1410	NO RECORDS

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/27/2009 7:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK 50 FT ABOVE THE PERFS AND CAP WITH 4 SKS OF CMT. REC. CASING. CIRC. CMT FROM 300'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE
Date/Time Plugging Completed: 08/27/2009 8:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 1760', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 1410', AND PULLED TO 305'-0'.

Perfs:

Top	Bot	Thru	Comments
1842	1856	CSG	

INVOICED
DATE 3/03/10
INV. NO. 2010060875

RECEIVED
FEB 18 2010
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING 60/40 4% GEL GPS: LAT: 37.317690, LONG: -97.165300

Plugged through: CSG

District: 02

Signed

(TECHNICIAN)

ix