

# 84.24

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-187-00252-00-00  
Spot: C Sec/Twnshp/Rge: 24-30S-39W  
2640 feet from N Section Line, 2640 feet from E Section Line  
Lease Name: COBB B Well #: 1  
County: STANTON Total Vertical Depth: 2592 feet

Operator License No.: 5952  
Op Name: BP AMERICA PRODUCTION COMPANY  
Address: 2225 W OKLAHOMA AVE  
ULYSSES, KS 67880

| String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|--------|-------|------------|-------------|-----------------|
| SURF   | 8.625 | 604        |             |                 |
| PROD   | 5.5   | 2558       |             | WITH 350 SX CMT |

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/10/2009 1:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/10/2009 3:30 PM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

SAND FILL TO 2300'. WELL SANDED IN TO 2330'. CASING LEAK @ 770'. RIH W/TBG TO 2300' & PUMPED 126 SX CMT. POOH W/TBG. TIED ONTO 5 1/2" & PUMPED 180 SX CMT. FILLED 5 1/2" CASING & CIRCULATED CMT OUT 8 5/8" & 5 1/2" ANNULUS.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 2558 | 2592 | OH   |          |
| 2384 | 2536 |      |          |

RECEIVED  
DEC 31 2009  
KCC WICHITA

INVOICED  
DATE 2/23/10  
INV. NO. 2010060750

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

*Jack MacClaskey*  
(TECHNICIAN)

RECEIVED  
DEC 18 2009

KCC DODGE CITY

*B*  
Form CP-2/3