

89.41

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-00347-00-00
Spot: NW Sec/Twnshp/Rge: 1-24S-38W
1320 feet from N Section Line, 1320 feet from W Section Line
Lease Name: MARTIN C Well #: 1
County: KEARNY Total Vertical Depth: 2751 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 W OKLAHOMA AVE
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2550		
SURF	8.625	815		WITH 400 SX CMT
PROD	5.5	2720	0	WITH 950 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/14/2010 9:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RON ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/14/2010 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2550'. RAN BOND LOG. TOC @ 200'. PERFORATE @ 170'. CIRCULATE CMT FROM 2500' TO 0' IN 2 STAGES WITH 270 SX CMT & 100# HULLS. STAYED FULL. CIRCULATE 15 SX CMT FROM 170' TO 0' IN 5 1/2" X 8 5/8" ANNULUS. PRESSURE TO 250#. HELD AT 100#.

Perfs:

Top	Bot	Thru	Comments
2698	2703		
2631	2692		
2580	2617		

INVOICED
DATE 2/23/10
INV. NO. 2010060750

RECEIVED
FEB 19 2010

KCC WICHITA

Remarks: USED CLASS C CMT W/2% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
(TECHNICIAN)

RECEIVED

JAN 28 2010

MD

KCC DODGE CITY

[Signature]