

\$ 101.73

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-23299-00-00  
Spot: SESWNW Sec/Twnshp/Rge: 25-33S-4E  
2965 feet from S Section Line, 4375 feet from E Section Line  
Lease Name: SEACAT Well #: 8  
County: COWLEY Total Vertical Depth: 3130 feet

Operator License No.: 32679  
Op Name: AAS OIL CO., INC.  
Address: 2508 EDGEMONT DR STE # 4  
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	256		125 SX
PROD	4.5	3125	277	300 SX

Well Type: EOR UIC Docket No: E21514.2 Date/Time to Plug: 01/19/2010 8:00 AM  
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.  
Proposal Rcvd. from: GARY ANSTINE Company: AAS OIL COMPANY INC Phone: (620) 442-7940

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/19/2010 5:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/CIBP ON WIRELINE AND SET @ 3,016', DUMP BAILED 2 SXS CEMENT ON TOP. PERFORATED SQUEEZE HOLES @ 306', CONSOLIDATED OIL WELL SERVICES SWEDGED INTO 4-1/2" CASING AND PUMPED 80 BBLs WATER, WELL WOULD NOT CIRCULATE. CUT CASING @ 277', LAYED DOWN CASING. RIH W/TBG @ 281', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION AND MIXED AND PUMPED 126 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 1/19/2010, 5:30 P.M. CEMENT TICKET #23165.

Perfs:

Top	Bot	Thru	Comments
3080	3086	CSG	2 SHOTS PER FOO

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 25 2010  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
DATE 2/23/10  
INV. NO. 2010060752

Remarks: E-21.514

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

JK