

#104.23

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20405-00-00
Spot: NESWSW Sec/Twnshp/Rge: 15-22S-2W
908 feet from S Section Line, 4016 feet from E Section Line
Lease Name: GRABER R Well #: 1
County: HARVEY Total Vertical Depth: 3207 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	212		150 SX
PROD	4.5	3206	247	75 SX

Well Type: GAS UIC Docket No: Date/Time to Plug: 01/26/2010 10:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: DOUG WARD Company: Phone: (620) 654-7149

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: Witness Type: PARTIAL
Date/Time Plugging Completed: 01/27/2010 10:45 AM KCC Agent: SHANE JONES

Actual Plugging Report:
1/26/2010 AMERICAN ENERGIES SANDED OFF BOTTOM. THEY THEN TIED ON TO PULL 450' OF THE 4.5" CASING. WHILE PULLING STRETCH CASING PARTED @ 247.5'. SO PULLED 247.5' OF 4.5" CASING. AT 3:00 PM THEY CALLED INTO THE KCC DIST 2 OFFICE AND TOLD US WHAT HAD BEEN DONE. THEY WANTED TO KNOW IF THEY COULD RUN 2" TUBING DOWN THE 4.5" TO 450' AND RUN 1" DOWN THE BACKSIDE TO 450' AND PLUG IT THAT WAY. THIS WAS APPROVED. 1/27/2010 I RECEIVED A CALL FROM THE OFFICE TO INFORM ME AMERICAN ENERGIES COULD ONLY GET DOWN TO 375' ON THE BACKSIDE WITH 1". IT WAS DISCUSSED WITH J KLOCK AND WAS APPROVED TO PLUG AT THIS POINT. WHEN I ARRIVED AT 9:00 AM AMERICAN ENERGIES HAD ALREADY TAGGED SAND @ 3080' AND CAPPED W/4SXS. THEY ALREADY HAD TUBING IN THE HOLE. COPELAND TIED ON TO THE 1" AND PUMPED 35 SXS TO FILL VOID ON BACKSIDE OF CASING. AMERICAN ENERGIES THEN PULLED THE 1" TUBING. COPELAND THEN TIED ON TO THE 2" TUBING AND CIRCULATED 165 SXS TO SURFACE. AMERICAN ENERGIES PULLED THE 2" AND FINISHED AT 10:45 AM. THEY USED A TOTAL OF 200 SXS OF 60/40 POS W/4% GEL TK #35829.

Perfs:


Top	Bot	Thru	Comments
3180	3184	CSG	MISSISSIPPI
3173	3176	CSG	MISSISSIPPI

RECEIVED
FEB 12 2010
KCC WICHITA

Remarks: GPS: LAT: 38.133000, LONG: -97.532540
Plugged through: TBG

INVOICED
DATE 2/23/10
INV. NO. 2010060753

District: 02

Signed  (TECHNICIAN)

JK