

107.54

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-20351-00-00
Spot: NWSWNESW Sec/Twnshp/Rge: 27-19S-1E
1707 feet from S Section Line, 3699 feet from E Section Line
Lease Name: KLASSEN Well #: 1
County: MARION Total Vertical Depth: 3309 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	207		UNKNOWN
PROD	4.5	3306	542	UNKNOWN

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: DOUG WARD Company: _____ Phone: (620) 654-7149

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 02/05/2010 10:30 AM KCC Agent: SHANE JONES

Actual Plugging Report:

2/2/10 AMERICAN ENERGIES SANDED OFF BOTTOM. 2/4/10 AMERICAN ENERGIES TAGGED SAND @ 3240' CAPPED WITH 4 SXS. RIG BROKE DOWN TOP PLUG POSTPONED TILL TOMORROW. AMERICAN ENERGIES GOT RIG FIXED. THEY CUT OFF AND PULLED 541.7' OF 4.5" CASING. 2/5/10 AMERICAN ENERGIES RAN 2" TUBING IN THE HOLE TO 300'. CAT PULLING COPELAND IN TO WELL SITE. COPELAND RIGGED UP AND CIRCULATED WATER. ONCE THEY GOT CIRCULATION SWITCHED TO CEMENT. COPELAND CIRCULATED CEMENT TO SURFACE. AMERICAN ENERGIES PULLED TUBING. THE HOLE WAS STILL STANDING FULL OF CEMENT. COPELAND USED 165 SXS 60/40 POS W/45 GEL. TICKET 34436.

Perfs:

Top	Bot	Thru	Comments
3299	3300	CSG	SIMPSON

RECEIVED
FEB 12 2010
KCC WICHITA

Remarks: GPS: LAT: 38.366990, LONG: -97.310740

Plugged through: TBG

INVOICED
DATE 2/23/10
INV NO 2010060753

District: 02

Signed



(TECHNICIAN)

14