

#114.92

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-19006-00-01  
Spot: NE Sec/Twnshp/Rge: 12-18S-16W  
3960 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: LEBSACK OWWO Well #: 1  
County: RUSH Total Vertical Depth: 3536 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1100		
SURF	15	406		CEMENTED IN
	11	1002		CEMENTED IN
PROD	7	3506	0	

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/31/2009 9:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.  
Proposal Rcvd. from: ALAN CURTIS Company: GRESSEL OILFIELD SERVICE, INC. Phone: (620) 463-5161

Proposed Plugging Method: SET CIBP @ 1100'. TEST CASING. PERFORATE @ 1020' & CIRCULATE CMT TO SURFACE OUT BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/31/2009 2:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 1100', TEST CASING TO 500#. PERFORATE AT 1015' & TRY TO PUMP INTO. PRESSURED TO 1000# & HELD. TRIED SEVERAL TIMES TO BREAK DOWN BUT COULDN'T. PERFORATED @ 750' & PUMPED INTO @ 1000# AT LESS THAN 1/2 BBL A MINUTE. RUN TBG TO 1020' & PUMP 190 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TIED ONTO CASING. PUMPED 15 SX CMT. PRESSURED TO 1000# & HELD. TIED ONTO BACKSIDE & PUMPED 75 SX CMT. CMT CAME OUT OF GROUND AROUND THE 2" RISER. SHUT DOWN.

Perfs:

Top	Bot	Thru	Comments
3343	3346		
1895	1900		

RECEIVED  
JAN 13 2010  
KCC WICHITA

INVOICED

DATE: 2/23/10  
INV. NO. 2010060754

Remarks: USED 60/40 POZMIX 4% GEL BY GRESSEL OIL FIELD SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
JAN 11 2010  
KCC DODGE CITY