

\$ 100.75

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21759-00-00
Spot: NE Sec/Twnshp/Rge: 33-17S-16W
1320 feet from N Section Line, 1320 feet from E Section Line
Lease Name: SCHEUERMAN Well #: 1
County: RUSH Total Vertical Depth: 3100 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2210		
SURF	8.625	1035		WITH 450 SX CMT
PROD	4.5	3062	0	WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/08/2010 2:00 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.
Proposal Rcvd. from: ALAN CURTIS Company: GRESSEL OILFIELD SERVICE, INC. Phone: (620) 463-5161

Proposed Plugging Method: PUMP HULLS IN FIRST OF CMT AND FILL TO TOP. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/08/2010 3:40 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CASING WAS PERFORATED @ 1966-76', 200 SX CMT PUMPED. MIXED 150# HULLS IN WITH 170 SX CMT. PRESSURED TO 300#. WENT ON SLIGHT VACUUM. PULLED SWEDGE OFF CASING & TOPPED OFF WITH 15 SX CMT. CASING STAYED FULL. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
3014	3018		
2070	2074		
1966	1976		
1947	1955		

INVOICED
DATE 2/23/10
INV. NO. 2012060754
RECEIVED

Remarks: USED 60/40 POZMIX BY GRESSEL OIL FIELD SERVICES.

Plugged through: CSG

JAN 13 2010

KCC WICHITA

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
JAN 11 2010
KCC DODGE CITY

Form CP-73