

86 13

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-22021-00-00
Spot: NWNWNEW Sec/Twnshp/Rge: 3-26S-5E
5191 feet from S Section Line, 3658 feet from E Section Line
Lease Name: WILKINSON Well #: 1
County: BUTLER Total Vertical Depth: 2650 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2602		
SURF	8.625	205		90 SX
PROD	4.5	2649		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/03/2009 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.
Proposal Rcvd. from: DICK SCHREMMER Company: BEAR PETROLEUM INC Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS, SAND PERFS TO 2250, & CAP W/4 SXS CEMENT. CIRCULATE 260'-0' W/ 60/40 POZMIX 4% GEL.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 12/03/2009 1:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2520', DUMP BAILED 4 SXS CEMENT ON TOP. PERFORATED CASING @ 260'-261'. RIH W/TBG @ 265', GRESSEL OILFIELD ESTABLISHED CIRCULATION, MIXED & PUMPED 85 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TBG, SWEDGED INTO 4-1/2" CASING AND FINISHED PUMPING 75 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED, PLUG DOWN 1:00 P.M. 12-3-2009.

Perfs:

Top	Bot	Thru	Comments
2605	2607	CSG	
2570	2573	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 25 2010
CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 2/23/10
INV. NO. 2010060754

Remarks: GRESSEL OILFIELD CMENET TICKET #34413.

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

✓