

#139.17

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-02686-00-01  
Spot: W2NENESW Sec/Twnshp/Rge: 18-10S-19W  
2310 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: L. SCOGGINS Well #: 9  
County: ROOKS Total Vertical Depth: 4282 feet

Operator License No.: 6931  
Op Name: BOWMAN OIL COMPANY, A GENERAL  
Address: 805 CODELL RD  
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1695	0	w/unknown sxs cmt
T1	2.875	1220		
PROD	5.5	4074	0	1800 SX

Well Type: SWD UIC Docket No: D02411.0 Date/Time to Plug: 02/10/2010 9:00 AM  
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: LOUIS "DON" BOWMAN O Company: BOWMAN OIL COMPANY, A GENE Phone: (785) 434-2286

Proposed	Ordered 350 sxs 60/40 pozmix - 4% gel - 800# hulls.
Plugging	Deep SWD plugged back to 1800' with cement May 12, 1982.
Method:	Cemented 8 5/8" & 5 1/2" to surface. Casing leak 900'. Decided to P/A.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/10/2010 11:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1230'.  
Allied pumped 20 sxs 60/40 pozmix - 4% gel neat - followed with 160 sxs 60/40 pozmix - 4% gel with 550# hulls.  
Circulated cement. PTOH. Squeezed 15 sxs cement - casing full.  
Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
1260	1280		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

RECEIVED  
FEB 22 2010  
KCC WICHITA  
INVOICED  
DATE 2/23/10  
INV. NO. 2010060755

District: 04

Signed Richard Williams  
(TECHNICIAN) CM

FEB 12 2010

SKELLY OIL COMPANY

#9

SCOGGINS

22 18-10-19W  
NE NE SW

Contr.

ROOKS

County

E 2230

Comm.

Comp.

1-13-50

IP

S W D W

Tops	Depth	Datum
HEEB	3446	-1216
TOR	3465	-1235
LANS	3483	-1253
CONG	3754	-1524
SIMP	3799	-1569
ARB	3817	-1587
T.D.	4282	-2052

Casing

8" 1695 CO 3989 - PERF 27 S,  
5" 4074 3702-07 - ACID 750  
SWB 23 BW/3 HRS  
SSO: DD 4282  
ACID 4000  
S W D W  
INPUT 150 B WTR/  
50 MIN


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS