

# 106.44

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-079-19038-00-00  
Spot: SESENE Sec/Twnshp/Rge: 3-23S-3W  
2310 feet from N Section Line, 330 feet from E Section Line  
Lease Name: STUCKY Well #: 1  
County: HARVEY Total Vertical Depth: 3275 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8	254		UNKNOWN
PROD	4.5	4274	605	UNKNOWN

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/11/2009 8:00 AM  
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION  
Proposal Rcvd. from: DOUG WARD Company: AMERICAN ENERGIES Phone: (620) 654-7149

Proposed Plugging Method: THE PERFS WERE COVERED WITH SAND TO 3169' AND CAPPED WITH 4 SKS OF CMT. RECOVER CASING, CIRC CMT FROM 550-0.

Plugging Proposal Received By: B. J. HOPE WitnessType: PARTIAL  
Date/Time Plugging Completed: 11/16/2009 2:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:  
THE PERFS WERE COVERED WITH SAND FROM 3274' TO 3169' AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS PULLED FROM 605' AND LAYED DOWN. TUBING WAS RUN TO 546', WHERE A 50 PLUG OF COMMON CMT WAS SPOTTED. THE PLUG WAS TAGGED 1.5 HRS LATER AND FOUND AT 400'. TUBING WAS RUN BACK IN THE HOLE TO THE TOP OF THE CMT PLUG AND CMT WAS CIRCD TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3230	3242		

RECEIVED  
FEB 18 2010  
KCC WICHITA


INVOICED

Remarks: COEPLAND CMTG #34405. COMMON AND 60/40

Plugged through: TBG

DATE 2/23/10  
INV. NO. 2010060757

District: 02

Signed   
(TECHNICIAN)

1/4