

9172

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-19109-00-00
Spot: SESWNE Sec/Twnshp/Rge: 18-21S-3E
2972 feet from S Section Line, 1673 feet from E Section Line
Lease Name: GOOD B Well #: B-4
County: MARION Total Vertical Depth: 2822 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8	110		UNKNOWN
PROD	5	2818	299	UNKNOWN

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/09/2010 10:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: DOUG WARD Company: _____ Phone: (620) 654-7149

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 02/09/2010 3:30 PM KCC Agent: SHANE JONES

Actual Plugging Report:

2/9/2010 AMERICAN ENERGIES MOVED IN AND CAPPED CIBP SET @ 1980 W/2SXS OF COMMON. THEY CUT OFF 5.5" CASING AT 299' AND PULLED IT OUT. THEY THEN RAN IN 270' OF TUBING. CONSOLIDATED TIED ON AND CIRCULATED CEMENT TO SURFACE. AMERICAN ENERGIES PULLED TUBING, AND CONSOLIDATED TOPPED OFF THE WELL. THEY USED 163 SXS OF 60/40 POS W/4% GEL TK #23376. THEY FINISHED AROUND 3:30 PM.

Perfs:

INVOICED
DATE 2/23/10
INV. NO. 2010060757

RECEIVED
FEB 22 2010

KCC WICHITA

Remarks: CIBP @ 1980' GPS: LAT: 38.22637, LONG: 97.13952

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

✓ JK