

7  
10488

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-115-20602-00-00  
Spot: SWNWSWNW Sec/Twnshp/Rge: 23-19S-1E  
3576 feet from S Section Line, 4994 feet from E Section Line  
Lease Name: BULLER Well #: 2  
County: MARION Total Vertical Depth: 3227 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200		
PROD	4.5	2946	477	

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/12/2010 8:00 AM  
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION  
Proposal Rcvd. from: DOUG WARD Company: \_\_\_\_\_ Phone: (620) 654-7149

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/15/2010 10:15 AM KCC Agent: SHANE JONES

Actual Plugging Report:  
2/12/2010 AMERICAN ENERGIES MOVED IN TO DO BOTTOM PLUG. THEY FOUND THE WELL BRIDGED OFF @ 600'. THEY SAND PUMPED THRU THE BRIDGE FROM 600' TO 850'. THEY GOT DOWN TO 2830' APPRO 30' BELOW THE PERFS. THEY DROPPED SAND. LATER IN THE DAY TAGGED SAND @ 2740' AND CAPPED WITH 4 SXS CEMENT. THEY THEN RIPPED CASING @ 475'. AMERICAN ENERGIES PULLED 477' OF 4.5" CASING. THEY THAN RAN IN 270' OF 2" TUBING, AND SHUT DOWN FOR THE WEEKEND. 2/15/2010 COPELAND ON SITE AT 9:00 AM. THEY TIED ON TO TUBING AND CIRCULATED CEMENT TO SURFACE. AMERICAN ENERGIES PULLED THE TUBING. THE HOLE WAS STILL STANDING FULL. THEY FINISHED AT 10:15 AM. THEY USED 160 SXS OF 60/40 POS 4% GEL TK #34445.

Perfs:

Top	Bot	Thru	Comments
2800	2802	CSG	MISSISSIPPI

INVOICED  
DATE 2/23/10  
INV. NO. 2010060757

RECEIVED  
FEB 22 2010

Remarks: 10 YEAR RULE GPS: LAT: 38.868500, LONG: -97.296930

KCC WICHITA

Plugged through: TBG

District: 02

Signed [Signature]  
(TECHNICIAN)

JK