

147.71

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21653-00-00
Spot: SWNWNWSE Sec/Twnshp/Rge: 35-33S-6W
2222 feet from S Section Line, 2485 feet from E Section Line
Lease Name: PULLIAM Well #: 2-35
County: HARPER Total Vertical Depth: 4545 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	251		300 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/24/2009 10:00 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: JOHN ARMBRUSTER Company: DUKE DRILLING CO. Phone: (620) 793-0840

Proposed Plugging Method: 35 SKS 1050', 35 SKS 700', 35 SKS 300' 25 SKS 60', 15 SKS RH, 10 SKS MH

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE
Date/Time Plugging Completed: 07/24/2009 12:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE DRL PIPE WAS RUN OPEN END TO 1050', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRILL PIPE WAS PULLED TO 700', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 300', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 60', WHERE CMT WAS CIRCULATED TO SURFACE. THE RAT HOLE WAS PLUGGED WITH 15 SKS OF CMT. THE MOUSE HOLE WAS CIRCD WITH 10 SKS OF CMT.

Perfs:
INVOICED
DATE 2/23/10
INV. NO. 2010060758
RECEIVED
JAN 27 2010
KCC WICHITA

Remarks: ALLIED CMT 32644 60/40
Plugged through: DP

District: 02 Signed [Signature] (TECHNICIAN)

Handwritten mark at the bottom of the page.