

1/9/75

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-21365-00-00  
Spot: NESEWNNE Sec/Twnshp/Rge: 30-32S-19W  
700 feet from N Section Line, 1510 feet from E Section Line  
Lease Name: REYNOLDS Well #: 3  
County: COMANCHE Total Vertical Depth: 5900 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5040		WITH 2 SX CMT
SURF	8.625	630		WITH 325 SX CMT
PROD	5.5	5895	2400	WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/23/2009 9:45 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: KEVIN WILES SR. Company: AMERICAN WARRIOR Phone: (620) 272-4996

Proposed Plugging Method: CIBP @ 5040' WITH 2 SX CMT. PLUG AT 990' WITH 15 SX GEL & 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: LINDLEY REIMER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/23/2009 10:35 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5040' WITH 2 SX CMT. 1ST PLUG AT 990' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 15 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5114	5118		
5106	5110		
5092	5102		

INVOICED

DATE 2/23/10  
INV. NO. 2010060758

RECEIVED  
JAN 04 2010  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GE L BY ALLIED.

Plugged through: TBG

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
DEC 29 2009 *MD*

KCC DODGE CITY