

# 78.49

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-21336-00-01  
Spot: NENENWSW Sec/Twnshp/Rge: 15-32S-41W  
2500 feet from S Section Line, 1250 feet from W Section Line  
Lease Name: MURPHY A Well #: 3  
County: MORTON Total Vertical Depth: 2415 feet

Operator License No.: 4549  
Op Name: ANADARKO PETROLEUM CORPORATI  
Address: PO BOX 1330  
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	782		WITH 510 SX CMT
PROD	5.5	2414	0	WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/14/2010 1:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. PLUG AT STUB WITH 50 SX CMT. PLUG AT 810' WITH 50 SX CMT. PLUG AT 480' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/14/2010 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

\*\*BOND LOG SHOWS THE 5 1/2" IS CEMENTED TO THE SURFACE. CASING PULLER HAD NO STRETCH) PUMP 200# HULLS & 50 SX CMT AT 2178'. MUD SPACER FROM 1600' TO 800'. PUMP 90 SX CMT FROM 800' TO 0'. PRESSURE TO 500# & HELD. PUMP 5 SX CMT DOWN 5 1/2" X 8 5/8" ANNULUS TO 2000#. TOP OFF 5 1/2" WITH 5 SX CMT TO 500#.

Perfs:

Top	Bot	Thru	Comments
2170	2178		

INVOICED  
DATE 2/23/10  
INV. NO. 2010060759

RECEIVED  
FEB 19 2010

Remarks: USED COMMON CEMENT BY SARGENTS.

KCC WICHITA

Plugged through: CSG

District: 01

RECEIVED  
JAN 28 2010

Signed

(TECHNICIAN)

KCC DODGE CITY

Form CP-2/3