

203.91

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-10260-00-00
Spot: NE Sec/Twnshp/Rge: 23-34S-27W
1220 feet from N Section Line, 1320 feet from E Section Line
Lease Name: MERKLE UNIT Well #: 1
County: MEADE Total Vertical Depth: 6274 feet

Operator License No.: 31134
Op Name: ARMOR PETROLEUM, INC.
Address: PO BOX 4625
WICHITA FALLS, TX 76308

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5970		WITH 2 SX CMT
SURF	8.625	1400		WITH 900 SX CMT
PROD	5.5	6219	2171	WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/04/2010 10:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: SAUL NAVARRETE Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5970' WITH 2 SX CMT. PLUG AT 1450' WITH 100 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 60' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/04/2010 3:30 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 5970' WITH 2 SX CMT. 1ST PLUG AT 1450' WITH 100 SX CMT. NO RETURNS. 2ND PLUG PULL TO 560' & PUMP 40 SX CMT. NO RETURNS. SHUT DOWN 3 HOURS. LET CMT SET. RAN SAND LINE & FOUND TOC @ 400'. PUMP 20 BBL GEL WATER. NO RETURNS. PULL TO 60' & PUMP 25 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
6114	6132		MORROW
6035	6039		CHESTER
6020	6026		

INVOICED
DATE 2/23/10
INV. NO. 2010060760

RECEIVED

JAN 13 2010

KCC WICHITA

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Jerry W. Stapleton
PIR-TX
(TECHNICIAN)

RECEIVED

JAN - 8 2010

KCC DODGE CITY

Form CP-3/3