

\$ 80.60

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-19186-00-01

Spot: NESENE

Sec/Twnshp/Rge: 32-17S-4E

3630 feet from S Section Line,

330 feet from E Section Line

Lease Name: RALPH NOVAK

Well #: 1

County: MARION

Total Vertical Depth: 2480 feet

Operator License No.: 34197

Op Name: ARBUCKLE ENERGY INC.

Address: 2914 ALOMA ST
WICHITA, KS 67211

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

SURF	10.75	185		
------	-------	-----	--	--

PROD	5.5	2425		
------	-----	------	--	--

Well Type: EOR

UIC Docket No: E04973.1

Date/Time to Plug: 02/02/2010 2:00 PM

Plug Co. License No.: 6819

Plug Co. Name: SCOTT'S WELL SERVICE INC

Proposal Rcvd. from: JAY SCOTT

Company: SCOTTS WELL SERVICE

Phone: (785) 254-7828

Proposed Plugging Method: PUMP 50 SXS CEMENT ABOVE TOP PERFS. PULL TUBING TO 250' AND CIRCULATE TO SURFACE. RUN 1" DOWN BACKSIDE TO 250' AND CIRCULATE TO SURFACE.

Plugging Proposal Received By: GREG EVES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 02/02/2010 4:00 PM

KCC Agent: GREG EVES

Actual Plugging Report:

Perfs:

RAN TUBING TO 2604' AND PUMPED 50 SXS CEMENT. PULLED TUBING TO 248' AND PUMPED 60 SXS TO CIRCUALTE TO SURFACE. PULLED TUBING OUT AND RAN 1" TUBING TO 100' IN BACKSIDE BEFORE HITTING CEMENT. PUMPED 50 SXS TO CIRCULATE TO SURFACE. PUMP 35 SXS TO TOP OFF.

RECEIVED

FEB 10 2010

KCC WICHITA

INVOICED

DATE 2/23/10

INV. NO. 2010060761

Remarks: CONSOLIDATED WELL SERVICE TICKET #23286. TOTAL = 195 SXS 60/40 POZ 4% GEL. GPS: LAT: 38.53222, LONG: -097.00475

Plugged through: TBG

District: 02

Signed

Meg Eves

(TECHNICIAN)