

\$ 87.90

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-20702-00-00
Spot: NENESE Sec/Twnshp/Rge: 13-23S-3E
2333 feet from S Section Line, 413 feet from E Section Line
Lease Name: HINZ Well #: 10
County: BUTLER Total Vertical Depth: 2520 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	170		150 SX
PROD	4.5	2519	920	37 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/02/2009 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: _____ Witness Type: NONE
Date/Time Plugging Completed: 07/02/2009 4:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

QUALITY SANDED OFF BOTTOM TO 2410' AND CAPPED W/4SXS CEMENT. QUALITY THEN TRIED RIPPING CASING @ 1210' WAS NOT FREE. QUALITY THEN TRIED RIPPING CASING @ 1050' WAS NOT FREE AT THIS DEPTH. QUALITY THEN RIPPED CASING AT 920'. QUALITY PULLED CASING FROM THIS POINT TILL THEY HAD APPROX 250' LEFT IN THE HOLE. AT THIS POINT QUALITY CIRCULATED CEMENT TO SURFACE. QUALITY THEN PULLED CASING AND TOPPED OFF WELL. QUALITY USED 75 SACKS 60/40 POS W/4% GEL. I CHECKED TOP PLUG ON 7/6/2009 FOUND TO BE APPROX 10' DOWN. QUALITY WELL CUT OFF BELOW GROUND AND FILL TO TOP WITH CEMENT.

Perfs:

Top	Bot	Thru	Comments
2488	2492		
2476	2480		

INVOICED

DATE 2/23/10
INV. NO. 2010060762

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 22 2009

Remarks: 2505' PBTD

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed [Signature]
(TECHNICIAN)

1/14