

7 116.03

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-00152-00-01
Spot: SWSWSW Sec/Twnshp/Rge: 6-11S-15W
330 feet from S Section Line, 4950 feet from E Section Line
Lease Name: CHRISLER ELLIOTT UNIT Well #: 2
County: RUSSELL Total Vertical Depth: 3570 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	180	0	w/unknown sxs cmt
PROD	4.5	3540	0	300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/22/2010 11:00 AM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: ROBERT GRANT Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/22/2010 3:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 1577' - pumped 80 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 691' - pumped 40 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing. Hooked onto 4 1/2" casing - pumped 280 sxs 60/40 pozmix - 4% gel.
Circulated up the 8 5/8" surface pipe. Closed valve on 8 5/8".
S.I.P. 200#.

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 01 2010
CONSERVATION DIVISION
WICHITA, KS

Perfs:

Top	Bot	Thru	Comments
3355	3359		
3329	3332		
3292	3297		
3282	3285		
3275	3281		
3251	3256		
3165	3167		
3144	3149		
3115	3119		
3083	3093		
2853	2859		

INVOICED
DATE 2/23/10
INV. NO. 2010060763

Remarks: LEASE ORIGINALLY KNOWN AS HACHMEISTER C-1. ALLIED CEMENTING COMPANY-TICKET #33756.

Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN) CM

