

117.88

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21826-00-00
Spot: E2NESENE Sec/Twnshp/Rge: 12-21S-13W
3661 feet from S Section Line, 248 feet from E Section Line
Lease Name: BROWN-CANNADY Well #: 2
County: STAFFORD Total Vertical Depth: 3627 feet

Operator License No.: 32741
Op Name: BLUEBIRD PRODUCTION, INC.
Address: PO BOX 459
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	336		
PROD	4.5	3626	2430	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/17/2009 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3340' & 4 SX CMT. PLGU AT 720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/17/2009 2:05 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3300' & 4 SX CMT WITH DUMP BAILER. 1ST PLUG AT 728' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3537	3543		
3523	3527		
3510	3516		
3430	3436		
3396	3402		

INVOICED

DATE 2/23/10
INV. NO. 2010060704

RECEIVED
DEC 24 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
DEC 18 2009
KCC DODGE CITY

Form CP 23