

6030561

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-195-21,758-00-00

~~NESUSU~~ SEC. 6, T. 12 S., R. 23 W.

990 feet from S section line

H290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name NIEDEUS "A" Well # 1

Operator: F & M OIL CO. INC.

County TREGO 150.80

Name & Address 422 UNION CENTER

Well Total Depth 4640 feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 5/8 feet 265'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor UNION DRILLING CO INC License Number 5103 Tag 4

Address WICHITA, KANSAS 67202

Company to plug at: Hour: AM Day: 29 Month: 8 Year: 19 85

Plugging proposal received from LYLE CARSON

(company name) UNION DRILLING CO INC. (phone) _____

were: 8 5/8 SET @ 265' WITH HOLE FULL OF MUD LESS THAN 36 VISC. MUD AND NO LOSS OR GAIN OF FLUID SPOT CEMENT PLUGS WITH DRILL PIPE. ORDER 190 SX. 60/40 PZ 676 GEL 3% CC 8 5/8 W.P. HALLIBURTON CEMENT CO.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 7:30AM Day: 29 Month: 8 Year: 19 85

ACTUAL PLUGGING REPORT SPOT D.P. @ 2030 DISPLACE 25 SX. CNT. MIX.

LAY DOWN D.P. TO 1025' DISPLACE 100 SX. CNT MIX + 1 SX. FLO SEAL.

LAY DOWN D.P. TO 265' DISPLACE 40 SX. CNT. MIX LAY DOWN D.P.

PUSH W.P. TO KELLY DEPTH FILL HOLE TO BASE OF CENLAR W/ 10 SX.

CNT. MIX. DISPLACE 15 SX. CNT. MIX. IN RATHOLE W/ JOINT OF PIPE

PLUG COMPLETE

Remarks: ELR ANHY 2029-71

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

DATE SEP 17 1985

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 10113

SEP 16 1985
09-16-1985
CONSERVATION DIVISION
Wichita, Kansas

8-29

27
9-13-85
mjt