

6 031419

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-065-01921-0000

SW SW NESEC. 18, T 10 S, R 25 W/EX  
2970 feet from S section line  
1310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5920

Lease Name Hanna Well # 1

Operator: Te-Pe Oil and Gas Co.  
Name & Address Box 522  
Canton, Ks. 67428

County Graham 132.92  
well Total Depth 4090 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 169

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Poe Services Inc. License Number \_\_\_\_\_  
Address Oberlin, Ks.

Company to plug at: Hour: \_\_\_\_\_ Day: 14 Month: Sept Year: 19 90

Plugging proposal received from Terry Bandy  
(company name) Te-Pe (phone) \_\_\_\_\_

were: 8 5/8 set at 169 cwc 130 sks. 5 1/2 set at 4083 w/125 sks. Perf 3820-4039  
Order sand and common cement. Pull pipe, order 250 sks 65/35 poz 10% gel 500 lbs.  
hulls Allied. Cement Co. Wellbrock Water Truck. Perf at 2195 anhy and shot at 1305.

Hole plugged thru casing as casing was pulled.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 7:00 PM Day: 14 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT Sand bottom back to 3770 w/5 sks common cement

on sand w/bailer. Recovered 615 of 5 1/2. Loaded casing w/100 sks cement blend to 1305; shot off

casing at 615, loaded 5 1/2 and circulated to surface. Laid down casing, filled casing  
displacement to surface used total 250 sks cement blend w/500 lbs. hulls mixed in

Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 3 1990

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED (If additional description is necessary, use BACK of this form.) observe this plugging.

Signed Carl Goodrow  
carl Goodrow (TECHNICIAN)

DATE 10-8-90

INV. NO. 29578