

15-065-20591-0001

8-27

4-032315

E-26,884

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-20,581

SW NW NW / 4 SEC. 18, 10, 25 W
4290 feet from S section line
4950 feet from E section line

Operator license# 5363

Lease: Custer Well # 3

Operator: Berexco, Inc.

County: Graham 131.92

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 4059 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 260 feet

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: Berexco, Inc. License# 5363

Address: P.O. Box 723 - Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 27 Month: August Year: 1998

Plugging proposal received from: Dennis Kirmer

Company: Berexco, Inc. Phone: 785-628-6101

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls - 16 sxs gel.
Work string.

9-17-98

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 6:00 P.M., Day: 27 Month: August Year: 1998

Actual plugging report: 8 5/8" set at 260' w/185 sxs cwc. 5 1/2" set at 4059' w/150 sxs.
P.B.T.D. 4045'. Prod. Perfs 3854' - 4029'. Stage collar at 2176' w/400 sxs cwc. Ran tubing to
3773' and spotted 50 sxs cement blend with 400# hulls mixed in. Pulled to 3161' and
displaced 16 sxs gel. Pulled to 2204' and circulated with 140 sxs cement blend with 100#
hulls mixed in. Lay down tubing. Squeezed 5 1/2" with another 25 sxs cement blend to Max.
P.S.I. 1000#. S.I.P. 800#. Test 8 5/8" to 400#. Cement at surface. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

INVOICED

DATE 9-18-98

INV. NO. 51320

Form CP-2/3