

15-065-20582-00-00

8-24

4-032313

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-20,582

NW SW NW /4 SEC. 18, 10, 25 W
3630 feet from S section line
4950 feet from E section line

Operator license# 5363

Lease: Custer Well # 2

Operator: Berexco, Inc.

County: Graham 131.95

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 4060 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 260 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Berexco, Inc. License# 5363

Address: P.O. Box 723 - Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 24 Month: August Year: 1998

Plugging proposal received from: Dennis Kirmer

Company: Berexco, Inc. Phone: 785-628-6101

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls - 18 sxs gel.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All [X], Part [], None []

9-17-98

Completed: Hour: 11:15 A.M., Day: 24 Month: August Year: 1998

Actual plugging report: 8 5/8" set at 260' w/160 sxs cwc. 5 1/2" set at 4059' w/100 sxs. P.B.T.D. 4027'. Prod. Perfs 3836' - 4012'. D.V. at 2180' w/400 sxs cwc. Packer left in the hole at 3790'+. Ran tubing and spotted 50 sxs cement blend with 500# hulls. Pulled 600' of tubing and displaced 25 sxs cement blend followed with 15 sxs gel to circulate. Pulled tubing and squeezed 5 1/2" with 125 sxs cement blend to Max. P.S.I. 1000#. S.T.P. 300#. Used total 200 sxs cement blend with 15 sxs gel with 500# hulls mixed in. Cement at surface in annulus. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

RECEIVED
KANSAS CORPORATION COMMISSION

INVOICED

DATE 9-18-98

INV. NO. 51321