

15-065-20567-00-00

8-27 4-032314

RCV'd
09-08-98

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-20,567

SW SW NW /4 SEC. 18, 10, 25 W
2970 feet from S section line
4950 feet from E section line

Operator license# 5363
Operator: Berexco, Inc.
Address: P.O. Box 723
Hays, Kansas 67601

Lease: Custer Well # 1
County: Graham 132.44
Well total depth 4075 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 256 feet

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Berexco, Inc. License# 5363

Address: P.O. Box 723 - Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 27 Month: August Year: 1998

Plugging proposal received from: Dennis Kirmer

Company: Berexco, Inc. Phone: 785-628-6101

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls - 16 sxs gel.
Work string.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All , Part [], None []

Completed: Hour: 12:40 P.M., Day: 27 Month: August, Year: 1998

Actual plugging report: 8 5/8" set at 256' w/160 sxs cwc. 5 1/2" set at 4075' w/100 sxs.
P.B.T.D. 4032'. Prod.Perfs 3789' - 4008'. Squeezed from 3444' to near surface with 515 sxs.
Ran work string to 3966' and spotted 50 sxs cement blend with 400# hulls. Pulled to 3346'.
Displaced 16 sxs gel. Pulled to 2199' and circulated with 135 sxs cement blend with 100#
hulls mixed in. Pulled tubing and squeezed 5 1/2" with another 15 sxs of cement blend to
Max. P.S.I. 800#. S.I.P. 400#. Squeezed 8 5/8" with 50 sxs cement blend to Max. P.S.I.
300#. S.I.P. 100#. Plug complete.

Remarks:
Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES NO _____
Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES , NO _____
Plugged through TUBING _____, CASING _____ Elevation: _____ GL

I did / did not [] observe the plugging.

Carl Goodrow
(agent)

INVOICED

DATE 9-18-98
INV. NO. 51323