

\$186.88

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20166-00-01
Spot: NESWSWNE Sec/Twnshp/Rge: 25-29S-33W
3173 feet from S Section Line, 2025 feet from E Section Line
Lease Name: H M DANIELS Well #: 2
County: HASKELL Total Vertical Depth: 5750 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4330		
SURF	9.875	1622		WITH 650 SX CMT
PROD	7	5585	1708	WITH 425 SX CMT

Well Type: EOR UIC Docket No: E25011.1 Date/Time to Plug: 01/20/2010 1:30 PM
Plug Co. License No.: 34091 Plug Co. Name: BLACKHAWK WELL SERVICE, LLC
Proposal Rcvd. from: BARRY WALTERS Company: BLACKHAWK WELL SERVICE, LL Phone: (785) 623-1066

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/20/2010 3:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

IST PLUG CIBP @ 4330'. RUN TBG & TAG CIBP. PULL TO 4326' & PUMP 20 SX CMT. PULL TO 2950' & PUMP 75 SX CMT. HOLE STAYED LOADED. 2ND PLUG TBG AT 1639'. PUMP GEL WATER THEN 50 SX CMT. 3RD PLUG PULL TO 711' & PUMP 50 SX CMT. 4TH PLUG PULL TO 55' & PUMP 20 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4894	4898		MARMATON
4464	4672		KANSAS CITY B

INVOICED
DATE 2/26/10
INV. NO. 2010060843

RECEIVED
FEB 08 2010
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed

Jerry W. Stapleton
(TECHNICIAN)
PART 2

RECEIVED

FEB - 1 2010

KCC DODGE CITY

RAW