

\$ 153.76

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22602-00-00
Spot: SWSESE Sec/Twnshp/Rge: 1-33S-10W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: HARBAUGH A Well #: 2
County: BARBER Total Vertical Depth: 4731 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4300		WITH 2 SX CMT
SURF	8.625	338		WITH 200 SX CMT
PROD	5.5	4730	3460	WITH 130 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/14/2010 9:00 AM

Plug Co. License No.: 34091 Plug Co. Name: BLACKHAWK WELL SERVICE, LLC

Proposal Rcvd. from: BARRY WALTERS Company: BLACKHAWK WELL SERVICE, LL Phone: (785) 623-1066

Proposed Plugging Method: CIBP @ 4300' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: LINDLEY REIMER
Date/Time Plugging Completed: 01/14/2010 11:45 AM

WitnessType: COMPLETE (100%)
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

CIBP @ 4300' WITH 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4360	4379		MISSISSIPPI

RECEIVED
FEB 08 2010

INVOICED KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

DATE 2/26/10
INV. NO. 2010060843

Plugged through: CSG

District: 01

Signed Stephen Pfeifer
(TECHNICIAN)

RECEIVED
JAN 28 2010
KCC DODGE CITY

AMP