

#133.25

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21562-00-00
Spot: S2SW Sec/Twnshp/Rge: 26-22S-16W
660 feet from S Section Line, 3960 feet from E Section Line
Lease Name: KACHELMAN Well #: 2
County: PAWNEE Total Vertical Depth: 4100 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3940		WITH 2 SX CMT
SURF	8.625	267		WITH 225 SX CMT
PROD	4.5	4080	1780	WITH 125 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/31/2009 2:30 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: DAVID HAYES Company: OIL PRODUCERS Phone: (620) 546-4456

Proposed Plugging Method: SAND BACK TO 3940' WITH 4 SX CMT OR SET CIBP @ 3940' WITH 2 SX CMT. PLUG AT 1020' WITH GEL WATER & 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 12/31/2009 6:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG SET CIBP @ 3940' WITH 2 SX CMT. 2ND PLUG PULL CASING TO 1010'.
LOAD HOLE WITH GELLED WATER & PUMP 50 SX CMT. 3RD PLUG PULL CASING
TO 296' & PUMP 50 SX CMT. 4TH PLUG PULL CASING TO 40' & PUMP 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4002	4007		CONGLOMERATE
3997	3999		CONGLOMERATE
3991	3994		CONGLOMERATE

RECEIVED
JAN 11 2010
KCC WICHITA

INVOICED

DATE 2/26/10
INV. NO. 2010060843

Remarks: USED 60/40 POZMIZ 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed Steve Durrant

(TECHNICIAN)

RECEIVED

JAN - 6 2010

KCC DODGE CITY