

\$ 142.⁶⁸

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21900-00-00
Spot: SW Sec/Twnshp/Rge: 8-26S-15W
1320 feet from S Section Line, 3960 feet from E Section Line
Lease Name: STAMBAUGH Well #: 1
County: PRATT Total Vertical Depth: 4390 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3985		
SURF	8.625	307		WITH 185 SX CMT
PROD	4.5	4389	2205	WITH 150 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 01/06/2010 10:00 AM
Plug Co. License No.: 34091 Plug Co. Name: BLACKHAWK WELL SERVICE, LLC
Proposal Rcvd. from: DAVID HAYSE Company: OIL PRODUCERS Phone: (620) 546-4456

Proposed Plugging Method: SET CIBP 50' ABOVE TOP PERF & PUT 2 SX CMT ON TOP OF CIBP. PLUG AT 990' WITH 10 SX GEL & 50 SX CMT. PLUG AT 340' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: LINDLEY REIMER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/06/2010 11:10 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3985' & 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 990' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4337	4352		KINDERHOOK CH
4036	4042		LANS-H

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 29 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

INVOICED

DATE 2/26/10
INV. NO. 2010060843

District: 01

RECEIVED

JAN 15 2010

KCC DODGE CITY

Signed

Stephen J. Pfeifer
(TECHNICIAN)

Form CP-23