

\$ 150.67

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21819-00-00
Spot: NWSENE Sec/Twnshp/Rge: 29-13S-31W
1525 feet from N Section Line, 900 feet from E Section Line
Lease Name: HESS 29A Well #: 2
County: GOVE Total Vertical Depth: 4636 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	219		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/09/2009 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: RODNEY FARR Company: RITCHIE EXPLORATION, INC. Phone: (316) 691-9500

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 12/09/2009 2:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st. Plug at 2350' w/25 sxs.
2nd. Plug at 1475' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

INVOICED
DATE 3/03/10
INV. NO. 2010060863

RECEIVED
DEC 21 2009
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Case Morris
(TECHNICIAN)

DEC 11 2009