

116. 35

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25945-00-00
Spot: NWNESESE Sec/Twnshp/Rge: 32-15S-16W
1080 feet from S Section Line, 550 feet from E Section Line
Lease Name: DOME Well #: 1-32
County: ELLIS Total Vertical Depth: 3580 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1005		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/30/2010 8:00 PM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: LOU Company: SAMUEL GARY JR. & ASSOCIATES Phone: (303) 831-4673

Proposed Plugging Method: Ordered 185 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 01/30/2010 10:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 3440' w/25 sxs.
2nd. Plug at 1055' w/40 sxs.
3rd. Plug at 374' w/80 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Perfs:

INVOICED RECEIVED
DATE 3/03/10 FEB 12 2010
INV. NO. 2010060868
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: DP

District: 04

Signed *Richard Williams*
(TECHNICIAN) cm