

\$39.07

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-20524-00-00  
Spot: SENWNWNE Sec/Twnshp/Rge: 28-34S-43W  
400 feet from N Section Line, 2000 feet from E Section Line  
Lease Name: LENCUT Well #: 2  
County: MORTON Total Vertical Depth: 1202 feet

Operator License No.: 31457  
Op Name: SAN MARCO PETROLEUM, INC.  
Address: 240 MILWAKEE ST 2ND FLOOR  
DENVER, CO 80206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	396		WITH 370 SX CMT
PROD	5.5	1186	0	WITH 475 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/27/2010 10:30 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. PLUG AT 420' WITH 50 SX CMT. CHECK BACKSIDE WITH CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/27/2010 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 200# HULLS & 25 SX CMT AT 1202'. GEL SPACER BACK TO 480'. TAG WITH FLOAT ON WIRELINE. FILL 5 1/2" CASING FROM 480' TO 0' WITH 57 SX CMT. PRESSURE TO 1000#. HOLDING AT 500#. FILL 5 1/2" X 8 5/8" ANNULUS WITH 11 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
1186	1202	OH	

INVOICED  
DATE 3/03/10  
INV. NO. 2010060869

RECEIVED  
FEB 19 2010

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

KCC WICHITA

District: 01

Signed

*Ken Jehlik*

(TECHNICIAN)

RECEIVED

JAN 28 2010

KCC DODGE CITY

Form CR-2/3