

\$125.78

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25943-00-00
Spot: NESWNENE Sec/Twnshp/Rge: 29-12S-19W
775 feet from N Section Line, 925 feet from E Section Line
Lease Name: FURTHMEYER Well #: 1
County: ELLIS Total Vertical Depth: 3870 feet

Operator License No.: 6509
Op Name: CLARK, JIM D. DBA CLA-MAR OIL, CO
Address: PO BOX 1197
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	226		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/22/2009 4:00 AM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: ROBERT STEVENSON Company: CLA-MAR OIL COMPANY Phone: (785) 625-3863

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with /14# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RAY DINKEL WitnessType: NONE
Date/Time Plugging Completed: 12/22/2009 5:15 AM KCC Agent: RAY DINKEL

Actual Plugging Report:
1st. Plug at 1510' w/25 sxs.
2nd. Plug at 803' w/100 sxs.
3rd. Plug at 276' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:
INVOICED
DATE 2/24/10
INV. NO. 2010060767

Remarks: ALLIED CEMENTING COMPANY.
Plugged through: DP

RECEIVED
JAN 08 2010
KCC WICHITA

District: 04

Signed Ray Dinkel
(TECHNICIAN) CM

JAN 05 2010