

\$ 151.78

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-00148-00-01
Spot: NENE Sec/Twnshp/Rge: 33-34S-4W
4620 feet from S Section Line, 660 feet from E Section Line
Lease Name: RHINO Well #: 1
County: SUMNER Total Vertical Depth: 4670 feet

Operator License No.: 3532
Op Name: CMX, INC.
Address: 1551 N WATERFRONT PKWY STE 150
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4670		
CIBP		4797		
PROD	4.5	4926		225 SX CMT.

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/27/2009 9:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORP Phone: (620) 886-5665

Proposed Plugging Method: CIBP ABOVE TOP PERFS AND 2 SKS CMT, RECOVER CASING. 35 SKS 950', 35 SKS 650, CIRC CMT FROM 320-0

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 10/27/2009 11:45 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4451', AND CAPPED WITH 2 SKS OF CMT. THE CASING WAS RECOVERED FROM 3200', AND PULLED FROM THE WELLBORE. TUBING WAS RUN TO 972', WHERE 35 SKS OF CMT WAS SPOTTED. THE TUBING WAS PULLED TOP 648', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 324', WHERE CMT WAS CIRCD TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4820	4825		
4804	4814	CSG	
4750	4790	CSG	
4690	4720	CSG	
4501	4520	CSG	

RECEIVED
JAN 14 2010
KCC WICHITA

INVOICED
DATE 2/24/10
INV. NO. 2010060768

Remarks: ALLIED CMTG 60/40 4% GEL 150 SKS PLUS 70 SKS

Plugged through: TBG

District: 02

Signed [Signature]
(TECHNICIAN)

SR