

\$ 175.00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21471-00-00
Spot: N2NWNE Sec/Twnshp/Rge: 6-34S-20W
4910 feet from S Section Line, 1831 feet from E Section Line
Lease Name: BUTTS Well #: 1
County: COMANCHE Total Vertical Depth: 5400 feet

Operator License No.: 31691
Op Name: CORAL COAST PETROLEUM, L.C.
Address: 8100 E 22ND ST N BLDG 600, STE R
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5300		WITH 2 SX CMT
SURF	8.625	601		WITH 207 SX CMT
COND	20	60		20 SX CMT.
PROD	5.5	5386	3000	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/08/2009 12:15 PM
Plug Co. License No.: 4072 Plug Co. Name: PLAINS, INC
Proposal Rcvd. from: HERB DURRANT Company: CORAL COAST PETROLEUM Phone: (316) 269-1233

Proposed Plugging Method: CIBP @ 5300' & 2 SX CMT. PLUG AT 900' WITH 15 SX GEL & 40 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/08/2009 1:40 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5300' WITH 2 SX CMT. 1ST PLUG AT 896' WITH 15 SX GEL & 40 SX CMT. 2ND PLUG AT 637' WITH 50 SX CMT. 3RD PLUG AT 297' WITH 40 SX CMT. 4TH PLUG AT 80' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5246	5254		

INVOICED
DATE 2/24/10
INV. NO. 2010060770

RECEIVED
DEC 24 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED
DEC 18 2009

Signed Eric MacLaren
(TECHNICIAN)

KCC DODGE CITY

Form GP-113